

CADET COLLEGE OKARA

ESTIMATE FOR RENOVATION OF LECTURE HALL, CADET MESS AND BARBER SHOP AT CADET COLLEGE OKARA

1. Providing and fixing false ceiling plaster of Paris.

Barber shop roof $16' \times 12' = 192$ sft

Total area 192Sft

2. Painting walls and three coat for ceiling paint with Grains finishing.

Barber shop 192Sft

3. Providing and laying master ceramic tile size 2x 2 Executive Bello (EBL) series on light color base class SB Flooring of approved color and shade laid over $\frac{1}{2}$ " thick cement plaster 1:2 i/c white cement, pigment and sealer for finishing the joints i/c cutting grinding where necessary complete in all respects and as approved by the Engineer Incharge (For Floor)

Barber shop = $16 \times 12 = 192$ Sft

Lecture Hall = $30 \times 30 = 900$ Sft

Total = 1092 sft

4. Providing and fixing Principal Office Door change with 12mm Glass

Principal office door $84'' \times 48'' = 28$ Sft

28Sft

5. Providing and fixing Barber Shop door of Glass 12mm

$8 \times 10 = 80$ sft

6. Providing and fixing Looking Glass

$2 \times 16 \times 4 = 128$ sft

7. Providing and fixing Cadet Mess aluminum door

$9 \times 22 = 198$ sft

$4 \times 22 = 88$ sft

Total 286 sft

Providing and fixing barber shop slab L.S

8. Providing and fixing pigeon holes in Barber shop L.S

Total =